

DOOR AND FRAME SCHEDULE

NO.	SIZE					FINISH	FRAME				DOOR AND FRAME				
	W/H		THK.	MAT.	TYPE		TYPE	MAT.	FINISH	JAMB	FRAME DETAILS	HDWR	RATING	REMARKS	
	W	H							WIDTH	HEAD	JAMB	THRESHOLD	SET		
E17	EXIST.	3' X 7'-0"				LIGHTLY SAND / APPLY TWO COATS POLYURTHANE - SATIN						2/A4.1	3		EXISTING
E18	EXIST.	3' X 7'-0"				LIGHTLY SAND / APPLY TWO COATS POLYURTHANE - SATIN						3/A4.1	3		EXISTING
E19	EXIST.	3' X 7'-0"				LIGHTLY SAND / APPLY TWO COATS POLYURTHANE - SATIN						3/A4.1	3		EXISTING
E20	EXIST.	3' X 7'-0"				LIGHTLY SAND / APPLY TWO COATS POLYURTHANE - SATIN							4		REUSE - REFINISH AFTER RELOCATION
E21	EXIST.	3' X 7'-0"				?							2		EXISTING
E22	EXIST.	3' X 7'-0"				LIGHTLY SAND / APPLY TWO COATS POLYURTHANE - SATIN							4		REUSE - REFINISH AFTER RELOCATION
E23	EXIST.	3' X 7'-0"				LIGHTLY SAND / APPLY TWO COATS POLYURTHANE - SATIN							4		REUSE - REFINISH AFTER RELOCATION
E24	EXIST.	3' X 7'-0"										2/A4.1	3		EXISTING
E25	EXIST.	3' X 7'-0"											2		EXISTING
E26	EXIST.	12' X 12'											3		EXISTING OVERHEAD DOOR
E27	EXIST.	12' X 12'											3		EXISTING OVERHEAD DOOR
E28	EXIST.	12' X 14'											3		EXISTING OVERHEAD DOOR
E29	EXIST.	12' X 14'											3		EXISTING OVERHEAD DOOR
E30	EXIST.	12' X 12'											3		EXISTING OVERHEAD DOOR
E31	EXIST.	12' X 12'											3		EXISTING OVERHEAD DOOR
E32	EX. GATE												3		

POLICE STATION ADDITION

100A		3' X 7'	2 1/4"	AL	C	PREFINISH	A2	AL	PREFINISH	4 1/2"	5/A4.0 SIM	5/A4.0 SIM	6/A4.0	14		
100B		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	7 5/8"	5/A4.1	1/A4.1	3/A4.1	18		
101A		3' X 6'-8"	1 3/4"	WD	A	STAIN	HM4	HM	PAINT	10"	1/A4.3	5 & 9/A4.3	12/A4.3	16	45 MIN.	
101B		3' X 6'-8"	1 3/4"	HM	B	PAINT	HM1	HM	PAINT	8 3/4"	3/A4.0	7/A4.0	11/A4.0	15		
102	REUSE E22			WD		SEE E22 ABOVE	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	4/A4.1	17		MODIFY EXISTING DOOR FOR NEW HARDWARE
103		2'-8" X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	4/A4.1	20		
104	REUSE E20			WD		SEE E20 ABOVE	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	3/A4.1	21		
105		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	4/A4.1	20		
106	REUSE E23			WD		SEE E23 ABOVE	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	4/A4.1	20		
107		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	4/A4.1	20		
108		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	4/A4.1	20		
109		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	4/A4.1	20		
110		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	2/A4.1	17		
111		3' X 7'	1 3/4"	WD	A	STAIN	HM2	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	3/A4.1	19		

FIRE STATION RENOVATION

114		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	8 1/4"	9/A4.1 SIM	9/A4.1	2/A4.1	7		
115		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	3/A4.1	13		
116		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	3/A4.1	13		
117		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	3/A4.1	13		
118		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	3/A4.1	13		
118A		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	8 1/4"	9/A4.1 SIM	9/A4.1	4/A4.1	12	20 MIN.	
118B		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	8 1/4"	9/A4.1 SIM	9/A4.1	4/A4.1	12	20 MIN.	
120		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	3/A4.1	13		
121		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	3/A4.1	13		
122		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	3/A4.1	13		
123		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 5/8"	5/A4.1	1/A4.1	3/A4.1	13		
124		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	8 1/4"	9/A4.1 SIM	9/A4.1	4/A4.1	13		
125		3' X 7'	2 1/4"	AL	C	PREFINISH	A8	AL	PREFINISH	6"	4/A4.2	2/A4.2 SIM 5/A4.2 SIM	8/A4.1	1		
128		3' X 6'-8"	1 3/4"	HM	B	PAINT	HM1	HM	PAINT	8 3/4"	4/A4.3	8/A4.3	11/A4.0 SIM	6		
129		3' X 6'-8"	1 3/4"	HM	B	PAINT	HM1	HM	PAINT	8 3/4"	3/A4.3	7/A4.3	11/A4.0 SIM	5		
132A		3' X 7'	1 3/4"	WD	A	STAIN	HM4	HM	PAINT	7 1/2"	11/A4.3	12/A4.3	3/A4.1	8	45 MIN.	
132B		3' X 7'	1 3/4"	WD	A	STAIN	HM4	HM	PAINT	5 3/4"	1/A4.4	5/A4.4 9/A4.4	2/A4.1	9		
134		3' X 7'	1 3/4"	WD	A	STAIN	HM2	HM	PAINT	5 3/4"	9/A4.1 SIM	9/A4.1	3/A4.1	10		
135		3' X 7'	1 3/4"	WD	A	STAIN	HM2	HM	PAINT	5 3/4"	9/A4.1 SIM	9/A4.1	3/A4.1	10		
136		3' X 7'	1 3/4"	WD	A	STAIN	HM2	HM	PAINT	5 3/4"	9/A4.1 SIM	9/A4.1	3/A4.1	10		
137		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 3/4"	9/A4.1 SIM	9/A4.1	3/A4.1	11		
138		3' X 7'	1 3/4"	WD	A	STAIN	HM3	HM	PAINT	5 3/4"	9/A4.1 SIM	9/A4.1	4/A4.1	7		

FINISH SCHEDULE


ROOM NO.	ROOM NAME	FLOOR	BASE	WALLS	CEILING	CLG. HT.	REMARKS
100	WAITING	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
101	CORRIDOR	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	9'-0"	
102	DISPATCH	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
103	SUPPLY	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	8'-0"	
104	EVIDENCE ROOM	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	8'-0"	
105	OFFICE	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
106	CONFERENCE / BREAK RM.	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
107	OFFICE	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
108	DIRECTOR'S OFFICE	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
109	ADMIN. SPEC.	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
110	IT ROOM	SEALED CONCRETE	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	9'-0"	
111	ADA LATRINE	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	GYP. BD. - EPOXY PAINT	2'X2' LAY-IN ACOUSTICAL	8'-0"	
112	CORRIDOR	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	12'-8"	
113	VENDING	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	9'-0"	
114	MECH./ELECT.	SEALED CONCRETE	NFW	EXIST. CMU/GYP. BD. PAINT	EXIST. CONC. JOIST / DECK PAINT	BOTTOM OF DECK - 14"-11" BOTTOM OF TEES - 13"-8"	
115	SLEEPING QUARTERS #1	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
116	SLEEPING QUARTERS #2	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
117	SLEEPING QUARTERS #3	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
118	SLEEPING QUARTERS #4	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
119	CORRIDOR	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
120	SLEEPING QUARTERS #5	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
121	SLEEPING QUARTERS #6	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
122	SLEEPING QUARTERS #7	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
123	SLEEPING QUARTERS #8	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
124	SLEEPING QUARTERS #9	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	10'-0"	
125	TV AREA	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	GYP. BD. - PAINT	2'X2' LAY-IN ACOUSTICAL	9'-0"	
126	DINING	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	GYP. BD. - EPOXY PAINT	EXIST. CONC. JOIST / DECK PAINT	7'-8"+/-	
127	KITCHEN	RESINOUS FLOORING - TYPE 'B'	4" RESINOUS TYPE 'B'	GYP. BD. - EPOXY PAINT	GYP. BD. - EPOXY PAINT	7'-8"+/-	
128	FOOD STORAGE	RESINOUS FLOORING - TYPE 'B'	4" RESINOUS TYPE 'B'	GYP. BD. - EPOXY PAINT	2'X2' LAY-IN ACOUSTICAL	8'-0"	
129	FIRE SPRINKLER	SEALED CONCRETE	4" RESILIENT	GYP. BD. - PAINT	PAINT DECK AND STRUTURE	VARIES	
130	EXIST. MECH / ELECT.	NFW	NFW	EXIST. / NEW CMU - PAINT	GYP. BD. - PAINT	VARIES	
131	WASHER / DRYER	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	EXIST. CMU/GYP. BD. EPOXY PAINT	2'X2' LAY-IN ACOUSTICAL	8'-0"	W1
132	EXIST. CORRIDOR	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	EXIST. CMU EPOXY PAINT	2'X2' LAY-IN ACOUSTICAL	VARIES	F1, W3
133	CORRIDOR	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	GYP. BD. - EPOXY PAINT	2'X2' LAY-IN ACOUSTICAL	8'-0"	
134	UNISEX LATRINE	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	GYP. BD. & RESINOUS WALL COATING, TYPE 'A'	2'X2' HI-HUMIDITY LAY-IN ACOUSTICAL GYP. BD. - EPOXY PAINT	8'-0" LAY-IN ACOUST. 7'-11" GYP. BD. - EPOXY PAINT	W2, C1
135	UNISEX LATRINE	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	GYP. BD. & RESINOUS WALL COATING, TYPE 'A'	2'X2' HI-HUMIDITY LAY-IN ACOUSTICAL GYP. BD. - EPOXY PAINT	8'-0" LAY-IN ACOUST. 7'-11" GYP. BD. - EPOXY PAINT	W2, C1
136	UNISEX LATRINE	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	GYP. BD. & RESINOUS WALL COATING, TYPE 'A'	2'X2' HI-HUMIDITY LAY-IN ACOUSTICAL GYP. BD. - EPOXY PAINT	8'-0" LAY-IN ACOUST. 7'-11" GYP. BD. - EPOXY PAINT	W2, C1
137	SUPPLY RM.	RESINOUS FLOORING - TYPE 'A'	4" RESINOUS TYPE 'A'	GYP. BD. - PAINT EX. CMU - PAINT	2'X2' LAY-IN ACOUSTICAL	8'-0"	
138	EXIST. STORAGE	SEALED CONCRETE	4" RESILIENT	GYP. BD. - PAINT EX. CMU - PAINT	2'X2' LAY-IN ACOUSTICAL	8'-0"	
139	EXIST. OFFICE	SOLID VINYL FLOORING-PLANK	4" RESILIENT	GYP. BD. - PAINT EX. CMU - PAINT	2'X2' LAY-IN ACOUSTICAL	8'-0"	
140	EXIST. APPARATUS ROOM	NFW	NFW	EXIST. AND NEW CMU. (SOUTH WALL), PAINT	NFW	VARIES	

REMARKS

- FLOOR
F1 PROVIDE 2" WIDE CONTRASTING COLOR STRIP AT STAIR NOSING FOR ENTIRE WIDTH
- BASE
B1 NOT USED
- WALL
W1 EXISTING CERAMIC TILE FROM APPROX. 4" ABOVE FLOOR TO REMAIN.
W2 SEE INTERIOR ELEVATIONS FOR LOCATION OF RESINOUS COATING ON WALLS
W3 PAINT EXISTING HANDRAILS AND SUPPORTS - MATCH EXISTING
- CEILING
C1 PAINTED ALUMINUM GRID SYSTEM
- NFW - NO FINISH WORK



CONSULTANTS
DCI, Inc.
Civil Engineer
ROBBINS ENGINEERING
Structural Engineer
TME, LLC.
MEPF Engineer



**Fire Station Renovation and
Police Station Addition**
Building 7200 - Camp Joseph T. Robinson
North Little Rock, Arkansas

REVISIONS

ISSUE DATE
JULY 1, 2016
PROJECT NO.
0901U

CONTENTS
DOOR & FINISH
SCHEDULES

SHEET NUMBER

A3.0